

ADDENDUM #1

Subject: Copper River Watershed EYOS Habitat Enhancement Project
SWS-CRP 20, 22, 25
Pre-Bid Meeting Questions and Addendum #1

Date: January 21, 2021

Questions

Number	Asked by	Question	Answer
1	John Hanson - Wilson	How can we generate / source the waterway bed fill and the rounded river rock materials?	We have removed rounded river rock from the bid documents and replaced with a mixture of riprap, class 1 and porous backfill material for the waterway bed fill material. Rounded river rock for banks and point bars have been replaced with Riprap, Class 1 and B.
2	John Hanson - Wilson	Section 201: Unclassified excavation—4"Y measurement: How are we to obtain it? Required to have survey on site?	DOWL will have inspectors on site the entire time who will work with the contractor on take-offs and quantity. Will review quantities as they are submitted for payment. Can do some computations on site to determine what's being taken out. Up to contractor to work with DOWL, to justify ahead of time and make sure we know what you're taking out and what's going back in so you can be paid appropriately.
3	John Hanson - Wilson	Section 201: Stone clearing and grubbing to happen before May 15, however we have only done clearing, and gravel grubbing to coincide with mobilization. Clarify just clearing before May 17	Updated specification Section 201 to clarify that <u>clearing</u> only to occur before May 1.