LOCATION MAP

Contract Drawings For


CORDOVA FISH PASSAGE IMPROVEMENT PROJECTS COPPER RIVER HIGHWAY - MP 17.7 18 MILE CREEK CROSSING - COP 20 U.S. FISH AND WILDLIFE SERVICE

SECTION 24, TOWNSHIP 16 SOUTH, RANGE 1 WEST, COPPER RIVER MERIDIAN, ALASKA DECEMBER 2020

PROJECT LOCATION		
ADF&G SITE NO.	CRWP ID	COPPER RIVER HWY MP
20100486	COP 20	17.7

DESIGN DESIGNATIONS	
AADT 2015	244

COVER SHEET



DRAWING INDEX

C2	GENERAL NOTES AND QUANTITIES
C3	SURVEY CONTROL
C4	EXISTING STREAM PLAN AND PROFILE
C5	STREAM PLAN AND PROFILE
C6	ROADWAY PLAN AND PROFILE
C7	STREAM DESIGN DETAILS
C8	STREAM SECTIONS AND DETAILS
C9	ESCP, STREAM DIVERSION & ROADWAY
	DIVERSION PLAN
C10	REVEGETATION PLAN

PREPARED BY:



	ESTIMATE OF QUANTITIES	S 	
ITEM NO.	ITEM DESCRIPTION	PAY UNIT	QUANTITY
201(9)	201(9) CLEARING AND GRUBBING LUMP		ALL REQUIRED
202(4)	REMOVAL OF CULVERT PIPE	LINEAR FOOT	57
203(3)	UNCLASSIFIED EXCAVATION	CUBIC YARD	1100
203(5A)	BORROW, SELECTED MATERIAL, TYPE A	CUBIC YARD	869
203(5B)	SUBBASE, GRADING F	CUBIC YARD	374
301(4)	AGGREGATE SURFACE COURSE, GRADING E-1	CUBIC YARD	44
602(2)	STRUCTURAL PLATE ALUMINUM PIPE ARCH, 57" SPAN, 38" RISE	LINEAR FOOT	66
602(4)	STRUCTURAL PLATE ALUMINUM BOX CULVERT, 15'-6" SPAN, 7'-3" RISE	LINEAR FOOT	75
611(1A)	RIPRAP, CLASS I	CUBIC YARD	132
613(2)	CULVERT MARKER POST	EACH	4
618(2)	SEEDING	POUND	2
620(1)	TOPSOIL (4")	SQUARE YARD	180
630(3B)	GEOTEXTILE, REINFORCEMENT, TYPE 2	SQUARE YARD	681
631(2)	GEOTEXTILE, EROSION CONTROL, CLASS 1	SQUARE YARD	70
640(1)	MOBILIZATION AND DEMOBILIZATION	LUMP SUM	ALL REQUIRED
641(3)	TEMPORARY EROSION, SEDIMENT AND POLLUTION CONTROL	LUMP SUM	ALL REQUIRED
642(1)	CONSTRUCTION SURVEYING	LUMP SUM	ALL REQUIRED
642(14)	AS-BUILT PLANS	LUMP SUM	ALL REQUIRED
643(2)	TRAFFIC MAINTENANCE	LUMP SUM	ALL REQUIRED
644(15)	NUCLEAR TESTING EQUIPMENT STORAGE SHED	LUMP SUM	ALL REQUIRED
672(1)	STREAM DIVERSION & DEWATERING	LUMP SUM	ALL REQUIRED
690(10)	WATERWAY BED FILL	LINEAR FOOT	117
690(12)	WATERWAY BANK REVEGETATION AND PROTECTION	LUMP SUM	ALL REQUIRED
690(13)	ROUNDED RIVER ROCK	CUBIC YARD	66

LEGEND	
	DESCRIPTION
	APPROXIMATE RIGHT-OF-WAY
•	CONTROL POINT
	ORDINARY HIGH WATER
	EXISTING CULVERT
-// // //	EDGE OF PAVEMENT
	EDGE OF GRAVEL/SHOULDER
$\sim\sim\sim$	EDGE OF VEGETATION
$-\cdots \longrightarrow -$	EXISTING THALWEG
	TOP OF BANK
	TOE OF SLOPE
	PROPOSED CULVERT
	WATERWAY BED FILL
V/////////////////////////////////////	WATERWAY BANK REVEGETATION AND PROTECTION
	RIPRAP
	ROUNDED RIVER ROCK
	AGGREGATE SURFACE COURSE, E-1
	SELECTED MATERIAL, TYPE A
	SUBBASE, GRADING F
	SEED
∞	BULK BAG COFFERDAM

	ABBREVIATIONS
ALCAP	ALUMINUM CAP
AVASP	AS VERTICAL AS SAFELY POSSIBLE
BFW	BANKFULL WIDTH
BOF	BOTTOM OF FOOTING
CFS	CUBIC FEET PER SECOND
CL	CENTERLINE
CMP	CORRUGATED METAL PIPE
CRH	COPPER RIVER HIGHWAY
ELEV	ELEVATION
ESCP	EROSION AND SEDIMENT CONTROL PLAN
HW/D	HEADWATER TO DEPTH RATIO
INV	INVERT ELEVATION
MIN	MINIMUM .
MP	MILEPOST
NTS	NOT TO SCALE
OHW	ORDINARY HIGH WATER
OSHA	OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION
Q	FLOW
ROW	RIGHT-OF-WAY
STA	STATION
TYP	TYPICAL
VAP	VERTICAL ADJUSTMENT POTENTIAL

TABLE 1			
COARSE MATERIAL: RIPRAP, CLASS I			
APPROX. SIZE	MASS (LBS)	% PASSING	
10"	50	100	
8"	25	50	

TABLE 2		
FINE MATERIAL: POROUS BACKFILL		
SIZE/SIEVE % PASSING		
100		
65		
50		
25		
15		

GENERAL NOTES

- 1. THE CONTRACTOR IS RESPONSIBLE FOR DETERMINING THE EXACT LOCATION OF ALL SITE FEATURES. IF THE CONTRACTOR DISCOVERS CONDITIONS OTHER THAN THOSE SHOWN ON THE PLANS, CONTRACTOR SHALL IMMEDIATELY NOTIFY THE OWNER'S REPRESENTATIVE.
- 2. COORDINATE CONSTRUCTION STAGING AND MOBILIZATION AREAS AND ACTIVITIES WITH OWNER'S REPRESENTATIVE.
- 3. COORDINATE WITH OTHER CONTRACTORS WHO MAY BE PRESENT.
- 4. EXERCISE CAUTION AND COMPLY WITH ALL APPLICABLE OSHA REQUIREMENTS FOR WORKING IN CONFINED AREAS.
- 5. STATIONING IS ALONG CENTERLINE OF STREAM OR ROADWAY.
- 6. VERIFY ELEVATIONS OF ALL PROPOSED STRUCTURES PRIOR TO CONSTRUCTION. REPORT ANY DISCREPANCIES FROM PLANS IMMEDIATELY TO OWNER'S REPRESENTATIVE.
- 7. CULVERT DESIGN LOAD: AASHTO LOADING HL-93, MINIMUM SOIL BEARING CAPACITY: 3,900
- 8. EXCAVATION AND COMPACTION:
 - A. REMOVE AND DISPOSE OF ALL ORGANIC OR OVER SATURATED SOFT MATERIAL, WHICH CANNOT BE COMPACTED.
 - B. BACKFILL SHALL BE PLACED AND COMPACTED WITH CARE AND SHALL BE BROUGHT UP EVENLY AND SIMULTANEOUSLY ON BOTH SIDES OF PIPE. MATERIAL TO BE COMPACTED TO 95% MAXIMUM DENSITY.
- 9. CULVERT INSTALLATION:
 - A. CULVERT JOINTS SHALL NOT LEAK.
 - CULVERT INFILL MATERIAL SHALL BE INSTALLED IN PIPE ACCORDING TO PLANS. MANUAL INSTALLATION IS REQUIRED.
- 10. ALL VEGETATION IN THE AREAS NOT AFFECTED BY WORK SHALL BE PRESERVED AND PROTECTED BY THE CONTRACTOR. RESEED ALL DISTURBED AREAS.
- 11. TWO CULVERT MARKERS WILL BE INSTALLED AT EACH CULVERT PER STD D-09.00.

TABLE 3 WATERWAY BED FILL	
12"	100
9"	85
6"	58
3"	49
1"	32
0.75"	23
#4	10
#10	6

TABLE 4		
ROUNDED RIVER ROCK		
SIZE/SIEVE	% PASSING	
12"	100	
9"	75	
6"	30	
3"	15	
J 1"	10	
0.75"	5	
#4	0	
#10	0	


THE FOLLOWING DOT&PF STANDARD DRAWING APPLIES TO THIS PROJECT: D-09.00 CULVERT MARKER POST


IMPROVEMENTS EEK - COP 20 AN 9 SSAGE CR. AND \exists PA \mathbb{H}

. 0 Z ∞ FISH FORK GENERAL ORDOVA Γ Ö

PROJECT 1136.63087.0 DATE DECEMBER 2020


C2 OF C10





CORDOVA FISH PASSAGE IMPROVEMENTS WEST FORK 18 MILE CREEK — COP 20 EXISTING STREAM PLAN AND PROFILE

C4 OF C10






COP PROFILE CREEK AND MILE LAN \Box $\frac{1}{\infty}$ STREAM FORK Γ

PROJECT 1136.63087.00 DATE DECEMBER 2020

O DOWL 2020 C5 OF C10




CORDOVA FISH PASSAGE IMPROVEMENTS WEST FORK 18 MILE CREEK — COP 20 STREAM DESIGN DETAILS

PROJECT 1136.63087.01
DATE DECEMBER 2020

© DOWL 2020

C7 OF C10



DETAILS AND SECTIONS

STREAM DIVERSION NOTES:


DUE TO PERMISSIVITY OF GRAVELS IN THE 18 MILE AREA, A COFFERDAM MADE OF SHEET PILE MAY BE NEEDED TO REDUCE GROUNDWATER FLOW INTO EXCAVATED AREA. TEMPORARY DIKES OR BERMS MAY BE USED TO ISOLATE THE WORK AREA FROM WATERS OF THE SURROUNDING AREA. THIS WORK MAY REQUIRE A DIVERSION OF STREAM WATER. THE DESIGNERS RECOGNIZE THAT DIFFERENT CONTRACTORS WILL HAVE VARIOUS APPROACHES FOR CONTROLLING WATER AND CONSTRUCTION SEQUENCING. THIS DIVERSION PLAN HAS BEEN DEVELOPED TO CHECK FOR CONSTRUCTABILITY AND AS A STARTING POINT FOR A CONTRACTOR-GENERATED PLAN. CONTRACTOR MUST SUBMIT DIVERSION PLANS TO ENGINEER FOR APPROVAL PRIOR TO IMPLEMENTATION.

DIVERSION PLAN:

- PLACE BARRICADES, SIGNS, AND TEMPORARY ROAD DETOUR IN COMPLIANCE WITH SPECIFICATIONS, ADOT&PF, AND MUTCD. COORDINATE WITH OTHER CONTRACTORS WHO MAY BE PRESENT.
- 2. CONSTRUCT VISQUEEN LINED DIVERSION CHANNEL WEST OF THE EXISTING CROSSING LOCATION.
- USE EXISTING 60" CMP IN DIVERSION CHANNEL TO PROVIDE VEHICULAR ACCESS. CONSTRUCT DIVERSION CHANNEL BANKS TO BE MINIMUM 1' HIGHER THAN THE TOP OF THE DIVERSION PIPE, IF USED
- 4. USE BULK BAGS (SUPERSACKS) TO DIVERT STREAM FLOW THROUGH DIVERSION CHANNEL. LOCATION OF DIVERSION CHANNEL IS APPROXIMATE AND SUBJECT TO SITE CONDITIONS.
- 5. CONSTRUCT THE NEW ALUMINUM BOX CULVERT.
- 6. INFILL CULVERT AND RECONSTRUCT CREEK CHANNEL AS SHOWN IN PLANS.
- 7. DIVERT CREEK FLOW THROUGH THE NEW ALUMINUM BOX CULVERT.
- 8. REMOVE EXISTING 60" CMP, FILL DIVERSION CHANNEL, AND INSTALL ALUMINUM PIPE ARCH OVERFLOW CULVERT.
- RECONSTRUCT CREEK CHANNEL AND BANKS AS SHOWN IN PLANS.
- 10. RECONSTRUCT COPPER RIVER HIGHWAY OVER THE NEWLY INSTALLED
- 11. STABILIZE AND REVEGETATE ALL REMAINING DISTURBED AREAS.
- 12. RETURN VEHICULAR TRAFFIC TO COPPER RIVER HIGHWAY.

ESCP AND DEWATERING NOTES:

- DEWATER TRENCH AND WORK AREA WITH PUMP HOSE IF REQUIRED.
- 2. ALL DISCHARGE POINTS REQUIRE PERMANENT OR TEMPORARY VELOCITY CONTROLS.
- 3. PROVIDE FOR SEDIMENT REMOVAL FOR ALL DEWATERING ACTIVITY PRIOR TO DISCHARGE FROM THE PROJECT INTO ANY WATER OF THE
- 4. PROVIDE SPARE (EXTRA) PUMPS FOR BOTH THE STREAM BYPASS PUMP AND DETWÄTERING PUMP.
- EXISTING RIPARIAN VEGETATION SHOULD BE PROTECTED TO MINIMIZE DISTURBANCE.
- SILT FENCING TO BE USED TO PREVENT DISTURBED SEDIMENT FROM ENTERING THE WATERBODY. ADJUST LOCATION AS NECESSARY AND AS DIRECTED BY THE ENGINEER DURING CONSTRUCTION.
- EROSION AND SEDIMENT CONTROL DEVICES SHALL BE INSPECTED AND MAINTAINED ON A DAILY BASIS, MAINTENANCE SHALL INCLUDE REMOVAL AND DISPOSAL OF ACCUMULATED SEDIMENT, CLEANING AND REPAIR OF DAMAGED SEDIMENT CONTROL DEVICES.
- ALL DISTURBED GROUND CAPABLE OF SUPPORTING VEGETATION SHALL BE REVEGETATED FOR FINAL STABILIZATION. ALL AREAS NOT REVEGETATED SHALL BE 100% COVERED BY ROCK OR OTHER PERMANENT NON-ERODIBLE MATERIAL. FINAL STABILIZATION SHALL BE AS APPROVED BY THE ENGINEER.



 \bigcirc

 \sim

COP ROADWA

Η

Ш CRI

 \mathbb{Z}


 ∞

 \bigcirc S

Ш

S

SSION &



PLAN FORK 18 MILE CINE

WEST PROJECT 1136.63087.01 DATE DECEMBER 2020 © DOWL 2020

SHEET C10 OF C10